


C:\USERS\FOWLER\DESKTOP\SAMPLE PROJECT - SOLIDWALL.DWG 1/13/2014 4:32 PM



THE UNDERSIGNED HEREBY APPROVES THE ATTACHED (4) PAGES
INCLUDING THE FOLLOWING:

- **VOLUME = 25,082 C.F.**
- **MAINLINE PIPE GAUGE = 16**
- **WALL TYPE = SOLID**
- **DIAMETER = 96"**
- **FINISH = ALT2**

CUSTOMER

DATE

ASSEMBLY

SCALE: 1" = 10'

VOLUME: 25,082 C.F.

LOADING: H20/H25

SYSTEM INV = 91.0

NOTES

- ALL RISER AND STUB DIMENSIONS ARE TO CENTERLINE.
- ALL ELEVATIONS, DIMENSIONS, AND LOCATIONS OF RISERS AND INLETS, SHALL BE VERIFIED BY THE ENGINEER OF RECORD PRIOR TO RELEASING FOR FABRICATION.
- ALL FITTINGS AND REINFORCEMENT COMPLY WITH ASTM A998.
- ALL RISERS AND STUBS ARE 2 7/8" x 1/2" CORRUGATION AND 16 GAGE UNLESS OTHERWISE NOTED.
- RISERS TO BE FIELD TRIMMED TO GRADE.
- QUANTITY OF PIPE SHOWN DOES NOT PROVIDE EXTRA PIPE FOR CONNECTING THE SYSTEM TO EXISTING PIPE OR DRAINAGE STRUCTURES. OUR SYSTEM AS DETAILED PROVIDES NOMINAL INLET AND/OR OUTLET PIPE STUB FOR CONNECTION TO EXISTING DRAINAGE FACILITIES. IF ADDITIONAL PIPE IS NEEDED IT IS THE RESPONSIBILITY OF THE CONTRACTOR.

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY

CONTECH

ENGINEERED SOLUTIONS LLC

www.ContechES.com

9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069

800-338-1122 513-645-7000 513-645-7993 FAX


CONTECH

CMP DETENTION SYSTEMS

CONTECH
CONTRACT
DRAWING

Ø96" UNDERGROUND DETENTION SYSTEM - 000000-001
SAMPLE PROJECT
ANYTOWN, USA
SITE DESIGNATION: UDS

PROJECT No.: XXXXXX	SEQ. No.: 001	DATE: 1/13/2014
DESIGNED: XXX	DRAWN: RTF	
CHECKED:	APPROVED:	
SHEET NO.: C1 OF 4		




FABRICATION BoM									
FITTING	TYPE	QTY	Ø	CORRUIGATION	GAGE	FINISH	WALL TYPE	LENGTH	TOTAL
BAND FASTENER	12" HUGGER		96	w/BAR BOLT & STRAP	16	ALT2			
GASKETS	FLAT		96	12" WIDE					

PROJECT SPECIFIC BILL OF MATERIALS
TO BE COMPLETED AT TIME OF CONTRACT
DRAWINGS

C:\USERS\FOWLERT\DESKTOP\SAMPLE PROJECT - SOLIDWALL.DWG 1/13/2014 4:32 PM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Cotech Engineered Solutions LLC ("Cotech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Cotech. Failure to comply is done at the user's own risk and Cotech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Cotech immediately for re-evaluation of the design. Cotech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.



- KEY**
- 1. RIGID OR FLEXIBLE PAVEMENT
 - 2. GRANULAR ROAD BASE
 - 3. 12" MIN. FOR DIAMETERS THROUGH 96"
18" MIN. FOR DIAMETERS FROM 102"
AND LARGER MEASURED TO TOP OF RIGID
OR BOTTOM OF FLEXIBLE PAVEMENT.
 - 4. SELECT GRANULAR FILL PER AASHTO M145
A1, A2 OR A3, OR APPROVED EQUAL.
PLACED IN 8" LIFTS (COMPACTED TO MIN.
90% STANDARD DENSITY PER AASHTO T99.)
 - 5. GRANULAR BEDDING, ROUGHLY SHAPED TO
FIT THE BOTTOM OF PIPE, 4" TO 6" IN DEPTH

FOUNDATION/BEDDING PREPARATION



PRIOR TO PLACING THE BEDDING, THE FOUNDATION MUST BE CONSTRUCTED TO A UNIFORM AND STABLE GRADE. IN THE EVENT THAT UNSUITABLE FOUNDATION MATERIALS ARE ENCOUNTERED DURING EXCAVATION, THEY SHALL BE REMOVED AND BROUGHT BACK TO THE GRADE WITH A FILL MATERIAL AS APPROVED BY THE ENGINEER. ONCE THE FOUNDATION PREPARATION IS COMPLETE, 4" - 6" OF A WELL-GRADED GRANULAR MATERIAL SHALL BE PLACED AS THE BEDDING.

BACKFILL

THE BACKFILL SHALL BE AN A1, A2 OR A3 GRANULAR FILL PER AASHTO M145, OR A WELL-GRADED GRANULAR FILL AS APPROVED BY THE SITE ENGINEER (SEE INSTALLATION GUIDELINES). THE MATERIAL SHALL BE PLACED IN 8" LOOSE LIFTS AND COMPACTED TO 90% AASHTO T99 STANDARD PROCTOR DENSITY. WHEN PLACING THE FIRST LIFTS OF BACKFILL IT IS IMPORTANT TO MAKE SURE THAT THE BACKFILL IS PROPERLY COMPACTED UNDER AND AROUND THE PIPE HAUNCHES. BACKFILL SHALL BE PLACED SUCH THAT THERE IS NO MORE THAN A TWO LIFT (16") DIFFERENTIAL BETWEEN ANY OF THE PIPES AT ANY TIME DURING THE BACKFILL PROCESS. THE BACKFILL SHALL BE ADVANCED ALONG THE LENGTH OF THE DETENTION SYSTEM AT THE SAME RATE TO AVOID DIFFERENTIAL LOADING ON THE PIPE.

OTHER ALTERNATE BACKFILL MATERIAL MAY BE ALLOWED DEPENDING ON SITE SPECIFIC CONDITIONS, AS APPROVED BY SITE ENGINEER.

1 BACKFILL DETAIL
C3 SCALE: N.T.S.



**CONNECTION DETAIL
SINGLE BOLT, BAR AND STRAP**

GENERAL NOTES

- BANDS ARE NORMALLY FURNISHED AS FOLLOWS:
12" THRU 48", 1-PIECE
54" THRU 96", 2-PIECE
102" THRU 144", 3-PIECES
- BAND FASTENERS ARE ATTACHED WITH SPOT WELDS, RIVETS OR HAND WELDS
- REROLLED ANNULAR END CORRUGATIONS ARE NORMALLY 2 2/3" x 1/2". DIMENSIONS ARE SUBJECT TO MANUFACTURING TOLERANCES

2 H-12 HUGGER BAND DETAIL
C3 SCALE: N.T.S.

C:\USERS\FOWLER\DESKTOP\SAMPLE PROJECT - SOLIDWALL.DWG 1/13/2014 4:32 PM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.			
If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.			
MARK	DATE	REVISION DESCRIPTION	BY

CONTECH

ENGINEERED SOLUTIONS LLC

www.ContechES.com

9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069

800-338-1122 513-645-7000 513-645-7993 FAX

CONTECH


CMP DETENTION SYSTEMS

CONTECH
CONTRACT
DRAWING

Ø96" UNDERGROUND DETENTION SYSTEM - 000000-001
SAMPLE PROJECT
ANYTOWN, USA
SITE DESIGNATION: UDS

PROJECT No.: XXXXXX	SEQ. No.: 001	DATE: 1/13/2014
DESIGNED: XXX	DRAWN: RTF	
CHECKED:	APPROVED:	
SHEET NO.: C3 OF 4		

CLUSERS\FOWLER\DESKTOP\SAMPLE PROJECT - SOLIDWALL.DWG 1/13/2014 4:32 PM




CONSTRUCTION LOADS

FOR TEMPORARY CONSTRUCTION VEHICLE LOADS, AN EXTRA AMOUNT OF COMPACTED COVER MAY BE REQUIRED OVER THE TOP OF THE PIPE. THE HEIGHT-OF-COVER SHALL MEET THE MINIMUM REQUIREMENTS SHOWN IN THE TABLE BELOW. THE USE OF HEAVY CONSTRUCTION EQUIPMENT NECESSITATES GREATER PROTECTION FOR THE PIPE THAN FINISHED GRADE COVER MINIMUMS FOR NORMAL HIGHWAY TRAFFIC.

PIPE SPAN, INCHES	AXLE LOADS (kips)			
	18-50	50-75	75-110	110-150
MINIMUM COVER (FT)				
12-42	2.0	2.5	3.0	3.0
48-72	3.0	3.0	3.5	4.0
78-120	3.0	3.5	4.0	4.0
126-144	3.5	4.0	4.5	4.5

*MINIMUM COVER MAY VARY, DEPENDING ON LOCAL CONDITIONS. THE CONTRACTOR MUST PROVIDE THE ADDITIONAL COVER REQUIRED TO AVOID DAMAGE TO THE PIPE. MINIMUM COVER IS MEASURED FROM THE TOP OF THE PIPE TO THE TOP OF THE MAINTAINED CONSTRUCTION ROADWAY SURFACE.


3 CONSTRUCTION LOADING DIAGRAM
C4 SCALE: N.T.S.



SECTION VIEW

REINFORCING TABLE				
Ø CMP RISER	A	Ø B	REINFORCING	**BEARING PRESSURE (PSF)
24"	Ø 4' 4'X4'	26"	#5 @ 12" OCEW #5 @ 12" OCEW	2,410 1,780
30"	Ø 4'-6" 4'-6" X 4'-6"	32"	#5 @ 12" OCEW #5 @ 12" OCEW	2,120 1,530
36"	Ø 5' 5' X 5'	38"	#5 @ 10" OCEW #5 @ 10" OCEW	1,890 1,350
42"	Ø 5'-6" 5'-6" X 5'-6"	44"	#5 @ 10" OCEW #5 @ 9" OCEW	1,720 1,210
48"	Ø 6' 6' X 6'	50"	#5 @ 9" OCEW #5 @ 8" OCEW	1,600 1,100

** ASSUMED SOIL BEARING CAPACITY



ROUND OPTION PLAN VIEW

SQUARE OPTION PLAN VIEW

NOTES:

- DESIGN IN ACCORDANCE WITH AASHTO, 17th EDITION.
- DESIGN LOAD HS25.
- EARTH COVER = 1' MAX.
- CONCRETE STRENGTH = 3,500 psi
- REINFORCING STEEL = ASTM A615, GRADE 60.
- PROVIDE ADDITIONAL REINFORCING AROUND OPENINGS EQUAL TO THE BARS INTERRUPTED, HALF EACH SIDE. ADDITIONAL BARS TO BE IN THE SAME PLANE.
- TRIM OPENING WITH DIAGONAL #4 BARS, EXTEND BARS A MINIMUM OF 12" BEYOND OPENING, BEND BARS AS REQUIRED TO MAINTAIN BAR COVER.
- PROTECTION SLAB AND ALL MATERIALS TO BE PROVIDED AND INSTALLED BY CONTRACTOR.
- DETAIL DESIGN BY DELTA ENGINEERING, BINGHAMTON, NY.

4 MANHOLE CAP DETAIL
C4 SCALE: N.T.S.

SPECIFICATION FOR CORRUGATED STEEL PIPE-ALUMINIZED TYPE 2 STEEL

SCOPE

THIS SPECIFICATION COVERS THE MANUFACTURE AND INSTALLATION OF THE CORRUGATED STEEL PIPE (CSP) DETAILED IN THE PROJECT PLANS.

MATERIAL

THE ALUMINIZED TYPE 2 STEEL COILS SHALL CONFORM TO THE APPLICABLE REQUIREMENTS OF AASHTO M274 OR ASTM A929.

PIPE

THE CSP SHALL BE MANUFACTURED IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF AASHTO M36 OR ASTM A760. THE PIPE SIZES, GAGES AND CORRUGATIONS SHALL BE AS SHOWN ON THE PROJECT PLANS.

ALL FABRICATION OF THE PRODUCT SHALL OCCUR WITHIN THE UNITED STATES.

HANDLING AND ASSEMBLY

SHALL BE IN ACCORDANCE WITH RECOMMENDATIONS OF THE NATIONAL CORRUGATED STEEL PIPE ASSOCIATION (NCSIPA)

INSTALLATION

SHALL BE IN ACCORDANCE WITH AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, SECTION 26, DIVISION II OR ASTM A798 AND IN CONFORMANCE WITH THE PROJECT PLANS AND SPECIFICATIONS. IF THERE ARE ANY INCONSISTENCIES OR CONFLICTS THE CONTRACTOR SHOULD DISCUSS AND RESOLVE WITH THE SITE ENGINEER.

IT IS ALWAYS THE RESPONSIBILITY OF THE CONTRACTOR TO FOLLOW OSHA GUIDELINES FOR SAFE PRACTICES.

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY

CONTECH
ENGINEERED SOLUTIONS LLC
www.ContechES.com
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

CONTECH
CMP DETENTION SYSTEMS
CONTECH
CONTRACT
DRAWING

Ø96" UNDERGROUND DETENTION SYSTEM - 000000-001
SAMPLE PROJECT
ANYTOWN, USA
SITE DESIGNATION: UDS

PROJECT No.: XXXXX	SEQ. No.: 001	DATE: 1/13/2014
DESIGNED: XXX	DRAWN: RTF	
CHECKED:	APPROVED:	
SHEET NO.: C4 OF 4		